(15)

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

DTS COPY

Name of Work:Road and Footpath maintenance in ward no.15 in Dasarahalli

Sl	Description of Work	Unit	Qty	Rate to be Quoted	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.	**Cum**	**72.00**		
2	Supplying fixing precast reinforement concrete slabs 10cm thick including cost of reinforecemet as per design and drawing material cost transpotation hire charges of machinery. Machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges labour charges of cost of all materials.	**Sqm**	**250.20**		

Signature of the Contractor

Executive Engineer
Dasarahalli Division

ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ: Nil

ರದ್ದುಗೊಳಿಸಿರುವ ಐಟಂಗಳ ಸಂಖ್ಯೆ: Nil

ಕಂಡಿಕೆ(30) ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು (ದಾಸರಹಳ್ಳಿ)ರವರು ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗ ಒಳಪಡಿಸಿ ಟಿ.ಎ.ಎಸ್ ಅನುಮೋದಿಸಿದೆ.
ಕರಡು ಟೆಂಡರ್ ಪೆಪ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ ತಿದ್ದುಪಡಿ ಇಟ್ಟಿದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ: Nil

ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ: Nil